App. F. IX-4.

1924-25 P2

Previous references.

PW 197 18
1-19
(3--17
11 78

(Misc)

File No. 79-24

Serial Nos. 1-14

Later references.

misc 242-28-16

misc 328-28-2,4-18,12,15&16

PW 130-38 (1-2)

GENERAL AND REVENUE SECRETARIAT.

Serial Nos. 14

Part B for Oct 26

SUBJECT

Estimate for Rs 15000/- for the construction of the Banaras Chatram

---

G.O.No 675-J/misc-79-14 d- 9.10.26

Sanctions the reconstruction of the Banaras Chatram at a cost of Rs15000/- a sum of Rs12000 being met from the Chatram Savings Fund remitted from the Funds

G. R S. 11] 1924-5

GENERAL AND REVENUE SECRETARIAT.

(Myz)

NOTES.

File No. 79-24

FILE HEADING.

Repairs ~~Damage~~ to the eastern portion of the chattram premises at Hanuman Ghat, Benares -

From

The Myz. Commr in Mysore,

No. C. 334 Dated 24-9-24 Received 26-9-24

Diary No. 377 Enclos. 1 Spare Copies Serial No. 1

BRIEF ABSTRACT OF LETTER.

Forwards in original report recd from the local agent of the chattram at Benares bringing to notice the damage caused by the heavy rains on the 6th, 7th & 8th instant to the eastern portion of the chattram premises and promises to submit a further report on the point after hearing from Mr Madhuram

NOTES AND ORDERS.

As the M.C. states that he has called for Mr. Madhuram's views in the matter and also for an estimate of the probable cost of the works to be done, the further report promised by him will be awaited.

NOTES—First Sheet.

Serial No.

Mr. Madhuram has already been paid Rs 2500/- for the repairs of the new chattram building and Rs 300/- recently for laying out pipe ~~etc~~. for payment of Munc. tax & for removal of dismantled materials.

SD 27.9.24 27.9.24

2. The further repairs proposed will be awaited.

1.10.24.

2nd member 5/10

3. Mr. Ramaswami the mistri may be reported for his work & the A D F N may be paid up to accounts

2/10 3.10

3.10.24.

4. D. F. N. is forwarded.

SD 5/10

6.10.24.

2nd member 180/6.10

5. ~~Dupe~~ Work done from 1st January to December

6/10

10/4/24

10.10.24.

DEWAN'S OFFICE, RECD. ON 11. OCT. 1924 Reg. No. 2863

File No. of 19

General Revenue Secretariat.

NOTE—Contn Sheet

Final Note by the Second Member of Council.

Subject:—

6. Damage caused by heavy rains to the eastern portion of the Gangatir Matt chattram premises at Hanumanghat, Benares.

---

7. The Muzrai Commissioner has submitted in original a report from Bhodayana Rama Sastry, the local agent of the chattram at Benares, stating that the eastern portion of the chattram premises was badly damaged by the heavy rains on the 6th, 7th and 8th September 1924 and that early steps have to be taken for the reconstruction of the damaged portion to prevent further damage and loss. Mr. Madhoram, who is reported to have inspected the building, has been asked by the Muzrai Commissioner to furnish an estimate of the probable cost of the work and its receipt is awaited.

8. I beg to submit the matter for the information of His Highness.

SECOND MEMBER OF COUNCIL.

6-10-24.

Submitted to His Highness.

9. I submit herewith a Final Note by the....Second... Member of Council on the subject of.....damage caused by heavy rains to the eastern portion of the Gangatir Matt chattram premises at Hanumanghat, Benares

for His Highness' gracious ~~approval~~ information.

Camp Mysore,
11th October 1924.

Dewan.

11 OCT 1924

Record of Cases submitted for the Orders of His Highness the Maharaja.

Subject.



Damage caused by heavy rains to the eastern portion of the Gangatir Matt chattram premises at Hanumanghat, Benares.

Order.

~~KRW~~

18/12/24

G. R. S. III-2]

Muzrai Secretariat | Muz. File No. 79 of 1924.

Serial No.

1. From D.O reed have been issued since January last calling the promised further report regarding the damage caused to our Chatram at Benares by the floods of September 1924. The M.C. sent an acd. intern reply on 6.4.25 that Mr. Narayana has been requested to intimate the result in the matter & that a reply will be sent as soon as one is received from him. The trial report has been received from the M.C. on this in portions & made 12 days [illegible]

Sub[d] for [illegible]

5.8.25

5.8.25

Rec. Asst.

13.8.25

6.8.25

REVENUE 6 AUG. 1925 SECRETARY.

2 From Mr. Madhoramsaw of Messrs. Maniram Harijiramsaw, [illegible] Benares., D.O.Nr. 735 & 29.9.25 states that he returned from tour only a few days [illegible] he inspected the [illegible] and that it will require [illegible] Rs 25000 to Rs 30[illegible] for the [illegible] repairs of the [illegible]

NOTE—Contn. sheet

WD 0561- GPB—3750—1 S 22

G. R. S. III-2]

Muzrai Secretariat | Muz. File No. 77 of 192[illegible]

Serial No.	
3	From the P. S. to H. H. to the [illegible] No. 9438/3-10-25. ~~To~~ Forwards for disposal extract from Mr Madhavarao's letter to the same effect as above.

D

15. 5

Q. 0.1-9/[illegible] 197-18-3
NOTE—Contn. sheet
DJ 9-6-19

WD 0561—GPB—3750—1 8 22

[App. F. III—2

General and Revenue Secretariat | File No. 79 of 1924

Serial No

18. What is the balance available at the Chahām Savings Fund & at the General Mursai Fund. after

21.10.25.

19. Item of

Item

20

General and Revenue Secretariat | Mcy File No. 79 of 1924

Serial No

21. For orders
24.10.25.

Rev-Secy) 22. The opinion of the Mcy Counsel may be invited - No report has been received from him - Vide his letter of 23.9.1924.

1st member)

23. The Supt. (Rec Branch) may please bring this up in person.

24. [I wish to know the reason for having (Mcy chalkram)
29/10
28.10.25.

Mcy 764-18 and all the recorded collections of Mcy 568-89 on the subject are put up
SD
2/11/25

25. [As the first member has gone for a holiday on casual leave, I regret I cannot submit this file.]

26. The previous Mcy Cir[cular] is contd in Mcy file No. 568 of 18, which subd in the Mcy Circular file which was finally closed Rs 300 vide Mcy No. 1-9/0.1.1

XD

App F. III— 1

File No of 19

NOTE—Cont sheet

General and Revenue Secretariat

Misc. File No 79 of 1926

Serial No

The Charge being met from
Rs 45'78 at the Chalkan credit.
" 15 425 credit granted to Chalkan in the Vali.
" 5000 Damodar Da Cunha.
" 5000 Mrs Krishna Salgaocar

Rs. 30,000

28. The new Chalkan building is just in proper condition at a further cost of Rs 3000 nearly on account of repairs.
29. As the building has recently been damaged by the floods, Mr. Madhavan considers that a new building has to be erected at a cost of about 30,000 Rs.

17.11.25

398/17.11

Pers: Circle B
Put me
Letter C

30. We have already spent about Rs 33 000 over this building. and I don't think it should be necessary to spend another 30000 Rs over it.
I think this is another case of supplementary grant put up a decent building at a cost of Rs 15000, as E. Sahib. The expenditure being met from the Chalkan saving

App. r. 111— 1

File No. of 19

NOTE— Contn. Shts

Serial No

c/f this proposal was sent with the approval
& order, but there was
ask 5 h aware. Then a pla
Estimate for a 5 cot
approval.

31. A D f N for Sanction is
be put up accord & so
approval

d
7
1.12.25.

2. A D. f. N is put up.

SD
2-12-25

3/12/25

33. Fair draft as noise.

3 12 25.

4. Fair draft put up.

3/12/25

5 12 25.

Rev - Dep.

1st Meeting

106/41 35.

4.12.25.

36. Remit is for ex for Sanction
& Decon

DSN
7.12.25.

7. D. S. N. is put up.

7/12

8 Dgwan.

7.12.25

Robe flapper Dept Subm.

3.12.25

DEVELOPMENT OFFICE.
8 DEC 1925
Rec. No. 4235

App. F. III—4]

WD 0569—GPB —40,000

File No. of 192

General and Revenue Secretariat

Serial No

NOTE—Contn. Sheet

Final Note by the First Member of Council.

Subject:—

39) Repairs to the Mysore State Chattram building near Hanuman-ghat at Benares.

40) In continuation of my Final Note dated 6th October 1924 about the damage done to the Chattram building at Benares during the heavy rains of September 1924, I beg to submit that Mr.Madho-ramsand who was asked to furnish an estimate of the probable cost of restoring the damaged portions of the building has, in his letter dated 28th September 1925 to the Private Secretary to His Highness and No.735 dated 29th September 1925 to the Revenue - Secretary to Government, stated that the chattram building having collapsed, "it is impossible and difficult to erect a building on the site with the old materials or to preserve the non-collapsed portions here and there as, most of the materials have become unserviceable", that it will cost Rs.25,000 to Rs.30,000 to re-erect the building and that to build one story alone would cost about Rs.20,000.

41) 2. The Chattram building in question was purchased in June 1919 for Rs.30,000 out of the savings of certain chattrams and charities in the State. Since then a sum of nearly Rs.3,000 has been spent on its repairs. Considering that the institution has hardly any money at its credit, I am of opinion that instead of spending another 25 or 30 thousand rupees over the building, it may be sufficient to provide for the construction of a decent building on the site at a cost not exceeding Rs.15,000 at the most, the amount being met from the Chattram Savings Fund or the State Muzrai grant of next year or from each of these sources in part.

42) 3. If this proposal meets with the approval of His Highness

the Muzrai Commissioner will be asked to obtain a plan and estimate for a building within the above amount and submit them for the - approval and orders of Government.

FIRST MEMBER OF COUNCIL.

5-12-1925.

Submitted to His Highness.

43) *I submit herewith a Final Note by the* FIRST *Member of Council on the subject of* Mysore State Chattram building near Hanumanji at Benares *for His Highness' gracious approval.*

Bangalore,
8th December 1[illegible]

Record of Cases submitted for the Orders of His Highness the Maharaja.

Subject.



44) Repairs to the Mysore State Chatiram near Hanuman Ghat at Benares.

Order.

45) ~~K R W 2~~
10/12/25

46) Revised
4D

47) [illegible]

315
14.12.25

[illegible] member

12.12.25

G. R. S. III-2]

General and Revenue Secretariat.

Muz File No. 77 of 19[illegible]

Serial No.	
	48) Draft letter to Muz. Govt in Tamil for approval.
	15/12/25 Tamil.
	Rev-Secy) 16.12.25
	1st member) 17/12
431/17.12	49)
4	To the Muz Govt no. 754 of 21.12.25 stating that Govt consider that a decent building at a cost not exceeding 1500 Rs will be sufficient & calls for a plan & estimate.
5	From the Muz Govt no. P.C. 36 of 25.4.26 & 30.4.26 stating that Mr Madhava has been addressed several times on the subject & his reply is awaited.
6.	From Mr R.N. Ray Engineering Contractor at Benares. letter of 10.3.26 (received on 4.5.26) Sub & Site plan & Construction plan of the Combs of the Chairman & requesting Sanction

NOTE—Contn. sheet.

orders

G. R. S. III·2]

Muzrai Secretariat | Muz. File No. 79 of 1924-25

Serial No.	
	D.o ℔ 30 ℈ 3.5.24.
7	To Mr. S. N. Lakshminarasabha B.A.B.L. Advt. & Ch: Engr: Send for scrutiny plans & estt. of the proposed Const.n of the Chattram. Status of his reins.
8	D.O from Mr Lakshminarasayya No. 496 ℈ 18.6.26. Sends 3 blue Prints of the Design of the proposed Chattram at Benares as well as the Estt. for Rs 15000/- &c 50) The Estimate for Rs 15000/- for the renovation of the chattram at Benares is for orders. In the last trial members found it to be said that the amount can be met from the Chattram fund & from the Muzrai Sch. (i.e. from Each of these Sources. part. 51) May the file be sent to the Muz Comr. for perusing Estimate sent by the Engr and for indicating the Sources from which be met? [illegible]

NOTE—Contn. sheet

WD 0361- GPB—3750—1 8 22

* Submission Note, page 11 of the notes.)

An Explanation

G. R. S. III-2]

General and Revenue Secretariat. Govt File No. 75 of 19

Serial No.

be received

51) The file, may, as suggested by the Supt. be unofficially sent to the Muz. Commr., for framing the estimate indicating the sources from which the cost is to be met.

Rev Secy 27/6

52) The design proposed may perhaps be submitted to the Dewan for approval

2nd member)

53) The question of funds may first be settled in consultation with the M.C

54 Draft

55) Exhibit is submitted, for approval.

Rev. Secy

58

56) Please acknowledge receipt of estimate & design & forward it to D.H.S if no acknowledgement has been already sent.

57) The receipt has been duly acknowledged by a D.O letter from Commissr (No. R 9 1-7-26, vide Je 1 P).

Rev. Secy

NOTE—Contn. sheet.

G. R. S. III-2]

General and Revenue Secretariat: | Mur File No. 79 of 1924

Serial No.

10 To Mur Commrs No 1782 6.7.26

States that an estimate for Rs 15,000 with the plan for the chattram building has been received & requests him to point out the source from which the amount is to be met.

Secy 9/7/11

7r The Mur Commr.
No P.C. 36 of 1925-26 of the 26th August 1926.

States that a sum of Rs 2500/- out of the balance at credit of the Benares Chattram and Rs. 6500. from the Chattram saving fund may be spared during the current year towards the Construction of the Mysore chattram at Hanuman Ghat Benares viz: the balance of Rs 6000/- being forced next year.

2500
12500
15,000

59) It has been ascertained that there is an accumulated ~~deficit~~ surplus of Rs 27,455 at the credit of the Chattram savings fund, according to the Pass Book maintained in the Mur. Commr's office in respect of this fund. Out of the said ~~deficit~~ surplus a portion of the amount now required, is to be debited to the ~~Surplus~~ Savings Fund. Next year, it seems advisable

NOTE—Contn. sheet.

G. R. S. III-2]

General and Revenue Secretariat.

File No. 79 – 24 of 19

Serial No.

(Rs 15000)
to sanction the whole amt to be met as follows:—

Rs 2500 from the fund at the credit of the Chatram

Rs 12,500 from the Chatram Savings fund accumulation.

(b) If this is approved, the Estimate for Rs 15,000 shall be Sanctd and Mr. R. N. Ray of Benares asked to complete the work as soon as possible, a Completion report being sent up to Govt in due course.

(c) Subject to orders.

BG
31/8/26

Refce:- Para 53 above.

Rev. Secy)

31/8

~~Recommended~~)

53 I beg to suggest that the savings at the credit of the Chatram fund Rs 27,458 may be utilised for the purpose as suggested above

2nd member)

Please ask Comptr to state what is the balance of the Chatram fund and note if there are any charges to be met from this balance

OFFICE OF THE SECRETARY COUNCIL
3 SEP. 1926
No. 1769

NOTE—Contn. sheet.

G. R. S. III-2]

General and Revenue Secretariat.

Secy. File No. 79 of 1924.

Serial No	
	658
	12 6/7. Sd. 6/7 180 6/7
12	To. The Comptroller. No 4698 7.9.26. Enquires what the balance of the Chattram Savings Fund now is and if there are any charges to be met therefrom:
13	Fr the Comptroller. No 411/7408 B 14.9.26 States that Chattram Savings Fund had a credit balance of Rs 20,677-3-8. on the 30th June 1926 and that there are no charges at present to be met therefrom.
	66. The balance at credit of the Chattram Savings Fund on 30-6-26. was Rs. 20677-3-8. and there are no charges to be met therefrom at present. Subd. with reference to 64. Sepd. Submitted for orders. 16/9 Rev. Secy 17/9
	By kind reference is invited to minute dated 4.9.26 (Para 64) the Comptroller says that Rs 20,677-3-8 was at credit of the Chattram Savings

NOTE—Contn. sheet.

VD 31261—GPB—10,000—17-12-25

App. F. III—2

General and Revenue Secretariat

Mis File No. 79 of 1924

Serial No

at the end of the last official year. It would appear from the Mr's letter (PWD) that the Benares Chathram had Rs 2798-5-2 at its credit on 30.6.26. As suggested by the Mr a sum of Rs 2500. out of this amount maybe utilised for the new buildings proposed to be erected and the balance found from the amount at the credit of the C. S. Fund.

Sri Lakshmi Narasamma has sent three blue-prints of the designs for the new Chathram with an estimate for Rs 15000 based on the schedule of rates furnished by Mr R.N. Ray, Engineer & Contractor of Benares. If the design is in accordance of the instructions of the Dewan conveyed through the Rev secretary, they may be approved and the necessary copies maybe sent to the Contractor as requested in this letter dated 10.3.26 for submission to the Municipal Council of Benares for necessary sanction. Perhaps the estimate may also be sent to the Contractor to see if it is alright before it is finally sanctioned so that no revision may be necessary.

GPS 17.9.26

2nd member)

Dewan) I agree. Action may be taken accordingly. GPS

(Mark) 20.9.26

To: Mr, Ebrahim Khan Sth

Sth for Hon Sth's sanction.

24.9.26

To: Submitted for Perusal of Dewan's orders

GPS 24.9.26

OFFICE OF THE SECOND MEMBER OF COUNCIL
21 SEP. 1926
No. 2194.

DEWAN'S OFFICE.
Received on
23. SEP. 1926
Reg. No. 2229

NOTE—Contd.

WD 01264—GPB—40,000—17-12-25

App. F. III—2]

General and Revenue Secretariat

File No. 79 of 192 4 - 1

Serial No.

DEWAN'S OFFICE.
Received on
28. SEP. 1926
Regd No. 2371

Final Note required by the Member in put up
68
375.

Put up DSN at once
CRR
27926
27/9

D. S. N is put up for approval.
27/9/26
Rev. Sec'y
27/9

CRR
27.9.26
27/9

Dewan)

NOTE—Contn. Sheet

Final Note by the Second Member of Council.

Subject:—

Reconstruction of the Mysore State Chattram at Benares, near Hanuman Ghat.

Page 15 of office notes

With His Highness' sanction, the Muzrai Commissioner was requested to submit a plan and estimate for the reconstruction of a chattram near Hanuman Ghat, Benares, in place of the one damaged, at a cost not exceeding Rs 15,000.

2. Mr. R. N. Roy, Engineer and Contractor, Benares, has accordingly submitted his plan and rates and on the basis of these, Mr. S. H. Lakshminarasappa has forwarded blue prints of the proposed chattram with an estimate for Rs 15,000.

3. The Benares Chattram has at its credit Rs 2,778 and as suggested by the Muzrai Commissioner, a sum of Rs 2,500 out of this amount will be utilized for the new building, the balance of Rs 12,500 being met from the amount at the credit of the Chattram Savings Fund.

4. The plan and the estimate are herewith submitted for His Highness' gracious approval. The work will be entrusted to Mr. R. N. Roy and he will be requested to submit Mr. Lakshminarasappa's plan to the Municipal Council of Benares for approval ~~for~~ before carrying out the work.

Bangalore,
25th September 1926.

MEMBER OF COUNCIL.

Submitted to His Highness.

I submit herewith a Final Note by the Second Member of Council, on the subject of reconstruction of the Mysore State Chattram at Benares, near Hanuman Ghat, for His Highness' gracious approval.

Mirza M Hasan —
Dewan.

Bangalore,
27th September 1926

27 9 26

Record of Cases submitted for the Orders of His Highness the Maharaja.

Subject.





Plan and estimate for the re-construction of the Mysore State Chattram at Benares.

Order.

KRM

2/10/2.

1

Put up

4/10

4/10

G. R. S. III-2]

General and Revenue Secretariat.

Muz File No. 77 of 1926

Serial No.

Draft sn 60

18/10/26 5/10/26

ESTABY.

No. 357

2591/5/10

Muz 5/10

Jt Secy. 2nd member 5/10

Issue as sanctioned

Muz 7/10

14

To, Mun Comm, Chief Engr & Comptr No 675-7 Dy 9.10.26

Sanctions in estimate for Rs 15,000, a Sum of Rs 12,500/- being met out of the funds of the Chattram Sarangs Fund. & requests the Mun Comm to entrust the work to Mr R.N. Roy who will be asked to submit Rs 12,5 plan to the Mun Council for approval out the

Ans this ref from

NOTE—Contn. sheet.

16830

No. C.336 of 24-25 Office of the Muzrai Commissioner in Mysore.

Dated Bangalore, 23rd September 1924.

From

K. Chandy, Esquire., B.A.,

Muzrai Commissioner in Mysore,

Bangalore.

Muzr. 79-24-1.

To

K. V. Anantaraman, Esquire., B.A.,

Secretary to the Government of

His Highness the Maharaja of Mysore,

Revenue Department.

Sir,

I have the honor to submit herewith in original report No.25 dated the 15th instant received from the local agent of the chattram at Benares bringing to notice to damage caused by the heavy rains on the 6th, 7th and 8th instant to the eastern portion of the chattram premises at Hanuman Ghat and stating further that if early action is not taken for the re-construction of this portion, the consequential loss would be heavy. He adds that Mr. Madhoram who inspected the building has promised to make a separate reference in the matter. I beg to state that this gentleman has this day been written to to communicate his views in the matter and also furnish an estimate of the probable cost for the work necessary. A furtner report will be submitted to Government on receipt of his reply.

I have the nonor to be,

Sir,

Your most obedient servant,

Muzrai Commissioner.

KSR.

C 3364 of 24-25

19.9.24

No: 25

19.9.24

Vasal

Bhagwan Das

Agent.

Book no. I. 4757

RECEIPT.

Bureau MUNICIPALITY.

Bhelupura

Rs 45/3/-

Received from Diwan Mirsaab estate
through Bodayan Rama Shastri Agent.

Rupees (in words) Rs Forty three & three annas only

account of Water 27-0-0
House 16-3-1

B 4/11

the period Arrears 31/3/25 & IVth Kist 25/26.

full payment of demand, ~~bill no.~~ ~~, dated~~

18.8.25

ONE ANNA

Executive Officer or Secretary

I—622 MF—1928.

No.

14918

GAIGHAT (BANGALIBARA)
BENARES

D. No. 390 Dated the 29th Sept 25

The Mukhtar Secretary
to
His Highness the Maharaja Saheb Bahadur
of Jaipore
Jaipore

Recd
3 OCT

Dear Sir, I beg to inform you that it is only few days since I returned from my tour. I had the great intention of coming there, with my younger brother Mukund Ram Bhai, on the auspicious occasion of Dassera and to talk with you over the building [redacted] and other matter personally, but my brother fell ill and therefore I had to abandon that proposal. Now he is quite well.

T 4/10

I beg humbly to say plainly that the long standing matter regarding Municipal Taxes have got now settled by paying a sum of Rs 43/3/-, the receipt thereof is enclosed herewith. Now the taxes for the Chhabani Building will have only to be paid and not for the adjoining portion which will be assessed on being newly built. But sorry to say that that matter remains yet to be settled.

Further in reply to your letter asking me for supplying estimates for the new building of the Hanumanghat Chhabani building and the adjoining portion, I beg to state that the roughly estimated cost for the erection from the beginning will be from Rs 25000/- to 30000/- Rs 20000/- will be required for building one story only as the old materials have now become quite unserviceable.

Will you please therefore request Maharaja Saheb to issue on my behalf the sanction and be pleased to send me order.

GAIGHAT (BANGALIBARA)
BENARES.

29

[illegible] that the work may be commenced
here to commence, [illegible] and [illegible] are
now over. I have sent a telegram to Bishop Westcott
also. Chhotaram will [illegible] on Saturday afternoon.

I hope you are doing well Pema, always
of your service.

I beg to remain
Sir,
Yours very faithfully,
Madhusudan Das

D.No. 315

Extract from letter dated 28th September 1925 from Mr.Madhoramsand, of Messrs Maniram Harjiwanram, Gaighat (Bangalibara) Benares, to the Private Secretary to His Highness the Maharaja of Mysore, Mysore.

5 OCT

Further I beg humbly say that the Hanuman Ghat Chatram Building has now collapsed and it is impossible and difficult to erect a building on the sight with old materials or to preserve the not-collapsed portion with repairs here and there as most of the materials have become unserviciable. The whole to be newly erected and the roughly estimated cost for this new work is from Rs.25000/- to 30000/-. To build one story would cost about 20000/-, but to build the whole would come under the above estimate.

Please request Maharaja Saheb Bahadur on my behalf for sanction and be pleased further to send me orders on the receipt of which it would be convenient for me to proceed with the work.

No 943

Forwarded, with compliments, to the Chief Secretary to the Government of Mysore, Mysore, for disposal.

The Palace, Mysore,
3rd October 1925.

Mirza M. Ismail
Private Secretary.

ST 6/10

App.F.VI-G1.] B650

SUBJECT

Diary No of letter replied to 395

General and Revenue Secretariat
(Muz)
, the 192

Date of issue 21-12-25

Signed by M. V. Vedavyasachar

Section Muz
File No. 39-24
Serial No. 6

No. 757

To The Munsif Commr in Mysore, Bangalore

Sir,

With reference to your letter no. C 334 of 24-25 & 24-9-24 ~~submitting in original the report~~ of the local agent of the chattram ~~at Benares bringing to notice~~ regarding the damage caused by the heavy rains to the eastern portion of the chattram premises at Hanuman Ghat and ~~stating~~ the Ad-Ameen that Mr. Madhavarao has been written to to inspect the building and communicate his views in the matter and also to furnish an estimate of the probable cost

List of enclosures

Copied by

Examined by 21/12

over

~~of the work necessary~~, I am directed to state that Mr. Madhavan in his letter of 28-7-25 to the Private Secretary to H. H. the Maharaja has roughly estimated the cost of erecting a new building at Rs 25000 to Rs 30000 and the cost of constructing one storey only at Rs 20,000. ~~and that Govt~~ ~~cannot consider that~~ ~~Govt have decided that~~ In view of the heavy expenditure already incurred in the purchase of the building and its repairs, Govt. cannot consider that it would be sufficient to provide for the construction of a decent building on the site at a cost not exceeding Rs 15,000 at the most, the amount being met from the Chattram Savings Fund or the State Hy: Grant of next year or from ~~each of~~ both these sources in part, as may be decided later. I am, therefore, to request you to obtain a plan & estimate for a building within the above amount, & submit them for the approval and orders of Govt.

I have etc

Secretary

16.12.25

16.12.25

15.12.25

11' 91

P.C.36 of 25.26 [illegible]

[illegible]

[illegible]

GEN. & REV. SECRETARIAT. 3-MAY 1926 MUZRAI D1278

Muz 79-24-5

[illegible]

GENL. & REV. SECTT. Bn. Muz 1 MAY 1926 G. D. SECTION.

[illegible]

Sir,

Referring to your D.O. [illegible] I am directed to say that the Government of Madras have already sanctioned the construction of a building (Remand Dormitory) at a cost not exceeding Rs.15000/-, I have to request that the plans, estimates addressed to on the subject may kindly be sent at the earliest convenience. He has already been requested to submit the plans etc. final report will be submitted.

I have the honour to be,

Sir,

Your most obedient servant,

V. Balasundaram

Asst. Secretary.

ASR.

C.No.7

4th April 26.

No 456

R. N. RAY.
ENGINEER AND CONTRACTOR

Registered.

BENARES.

The 30th March, 1926.

No 329

To

Mirza M. Ismail, Esq. B.A., O.B.E.,
Private Secretary to His Highness
The Maharaja of Mysore,
Mysore.

Dear Sir,

I beg to submit herewith the site plan and the ground floor plan of the proposed construction at Hanuman Ghat, together with a schedule of rates for the probable works in this connection for favour of your examination and sanction at your earliest convenience, so that I may proceed with your work up to Rs.5,000/- within this budget year.

I beg also to invite your attention that the plan is drawn in 1/5th scale according to the Municipal By-laws, includes the re-modelled construction of the gate way on the South and a new step way with gate on the North, that is from the Harish Chandra Ghat. Please, therefore, order the Drawing Office for elevation and supplying me with 6 copies of ferro of the each plan for submission

C.No.7

4th April 1936.

(2)

R. N. RAY.

(CONTINUATION)

To

Mirza M. Ismain Yasu,B.A.,O.B.E(continued)

the Municipal Board for an early sanction in order that the work may be taken up in the hot season and the roof may be completed during rains. I, therefore, hope you will be very good enough to let me have your early order.

Yours faithfully,

R N Ray

Enclosrs: 2 Plans.)
1 Schedule of rate)
(in 3 sheets)

C.No.7

4th April 19 6.

No.520.

R. N. RAY.
ENGINEER AND CONTRACTOR.

BENARES.

The Court Bazar, Cantonment,

To

Mirza M. Ismail Esqr., B.A., C.I.E.,
Dewan of Mysore,
Mysore.

To 4
3.5.06

Mahroop Esq
Do you kindly
bring me up?
JM
2/5

Dear Sir,

In obedience to your command while in Benares I sent plans and rates for the proposed construction of the Chhattra building of the Sirbe at Hanumangat, Benares, under registered cover on 11-3-06, but I regret to inform you that I have not been favoured with an acknowledgment as yet. May I, therefore, request you to despatch the plans of elevation touched with the architecture of the South with your approval at your very early convenience.

If the work be taken up in April, it may be possible to extend the roofs in rains and complete the building in October next if funds permit. It is necessary that the foundation should be built before the rains during the rains. I trust you will take the above circumstances into your kind consideration and let me know before long.

C.No. 7

4th April 19 6.

(2)

R. N. RAY.

(CONTINUATION.)

To

Mirza M. Ismail Esqr., B.A., C.P.S.(continued)

Awaiting your commands,

I remain,

Yours faithfully,

C.No.7

4th April 1946.

Dear Mr. Ray,

I write to thank you very much for your letter of the 19th March and the site plan of the Hanuman Ghut Chattram. I shall hope to write to you again about the plans shortly in May.

Yours sincerely,

Lawrence M. Jamieson

B. Srinivas Iyengar, Esq., B.A., B.L.,
Revenue Secretary to Government.

REVENUE SECRETARIAT

Dated Bangalore, 3rd May 1926

DO - Loo 30 Encl. 2 Plans 2

Immediate.

d 7.5.26

May 79-2n-7

Dear Sir,

I am desired to enclose for favour of your scrutiny and return with your remarks plans and rates for the proposed construction of a Chettram building on behalf of the Mysore State at Hanuman Ghat, Benares. The idea is that the building should have the peculiar south indian style and should stand out among other buildings in the locality.

The matter is urgent and I shall be obliged if your will kindly furnish your views in the matter very early.

Yours Sincerely,

h

Sd/- Lakshminarasappa
Asst. to the Chief Engineer

S. H. Lakshminarasappa, Esq., B.A., B.L.,
Assistant to the Chief Engineer of Mysore,
Bangalore.

App F.VI G1.] B650

SUBJECT

Diary No of letter replied to

General and Revenue Secretariat
( )
, the 192

Date of issue 13/5/26

Signed by JMR, B.S.
Draft Rem: & appl
endorsed by the
Rev Secy: in person
for approval.
Sd/ 12/5 Rev Secy 12/5

12/5

Issue 12/5

List of enclosures —

Copied by RS.

Examined by

Section Jms

File No. 7-

Serial No. 12

D.O. No. 1457

To [illegible]

Dear Sir,

I am directed to refer to your D.O. letter No. 30 dated 22nd May 1926 inviting the Government's remarks regarding the construction of the Hanuman Ghat-Chatram at Benares, and request to be informed when your reply may be expected.

Yours [illegible]

12/5

S. A. Lakshmanarao appears to be the

over

Sir he as in medial

D.O.No. ~~1496~~

En 68 Office of the Chief Engineer of Mysore.

Dated Bangalore, ~~17~~th June 1926. May 79-24-B

68

Dear Mr. Ranganatha Row Saheb,

As desired in your D.O.letter No.30 dated 3rd May 1926, I send herewith 3 blue prints of the proposed Design for ~~construction of~~ Mysore Chattram building at Hanuman Ghat Benares together with an estimate for Rs.15,000/- for the same based on the schedule of rates furnished by the Engineer and Contractor, Mr. R.N. Ray, Benares.

The receipt of the plans and estimate may kindly be acknowledged.

The two plans and the schedule of rates received with the above letter are herewith returned.

Yours sincerely,

S.K. Lakshmana Rao

(X)
Enclosures - 3 Blue prints -
2 Paper plans
1 Schedule of rates -
1 Estimate

D.O. Camp No. R 1-7-26

ROUTINE NOTES.

requisitions etc., not intended for [illegible]

Camp No. R Mysore xxxxxxx 1st July 1926

mar 79 94 9

Dear Sir,

I am desired to acknowledge receipt of your D.O. letter No. 496 dated 18th June 1926 with its enclosures:

3 Blue Prints
2 Paper plans
1 Schedule of rates
1 Estimate

6

Yours sincerely,

To

S.H. Lakshminarasappa, Esq., B.A., B.E., &c.,
Assistant to the Chief Engineer of Mysore
Camp, Mysore.

Please acknowledge
Sri Lakshminarasappa
letter today

acknowledged in D.O. Camp No. R letter No. R 1-7-26 issued today.

1 slips noted on

G. R. S. III—3]

ROUTINE NOTES.

[To be used only for notes, requisitions etc., [illegible] for printing Board.]

N. B. -Shouldroutine notes be written on small slips
the notes must b cipoed, or slips pasted on
this form.

APP. F. VI. Gl.]

SUBJECT.....

.....

.....

Section Mug

File No. 77-24

Serial No. 10

Diary No. of letter replied to.....

No. 17

To

The Mysore Comr

General and Revenue Secretariat

( )

the *192*

Date of issue. 6th July 1926

Signed by Rt Navasimhan Naidu

Sir

With reference to correspondence ending with your letter no 7.C 36 of 1925-26. of the 30th April 1926 on the subject of the Mysore chattram at the Hanumanghat, Benares, I am directed to state that a plan & estimate for Rs 15000/- prepared by Mr R.A. Ry. Engineer Contractor at Benares as loan raised from Govt for the chattram at Benares has been scrutinised by the Chief Engineer,

Received by M.S.M. Lakshminarasappa on the basis of rate communicated by M. Rao Raja

6 July

List of enclosures.....

Copied by.....

Examined by.....

over

WD 01265—GPB—31,000—24-12-25

~~under the Circumstances I shall~~

and to request you to let me know

as to ~~State~~ the ~~amount~~ ~~of~~ ~~funds~~ ~~in the Treasury~~ ~~from which the cost may be met~~ amount

~~met~~ from what source this is to be met.

A very early reply is requested.

Thanks &c

GR
5726

Secretary to Treasurer

Rec'd 8/7/26

8/7

1117?

No. P.C 36 & 25.26 Office of the Muzrai Commissioner in Mysore

Dated Bangalore, 26th August 1926

GEN. & REV. SECRETARIAT
30 AUG 1926
MUZRAI

From

B. Ramaswamaiya, Esq., B.A., B.L.,
Muzrai Commissioner in Mysore,
Bangalore.

To

G.V. SECTT.
DR
28. AUG. 1926
G. D. SECTION.

C. Ranganatha Rao Saheb, Esq., B.A., B.L.,
Secretary to the Government of
His Highness the Maharaja of Mysore,
Revenue Department.

Sir,

With reference to your letter No.17/M.F.79-24 dated 6th July 1926 in re the source from which the sum of Rs.15000/- required for the construction of the Mysore Chattram at Hanuman Ghat-Benares City, may be met, I have the honor to state that out of Rs.2778-5-2 ------ available at the credit of the Benares chattram on 1st July 1926, a sum of Rs.2500/- together with a sum of Rs.6500/- from the chattram Savings Fund may be spared during the current year thus making a -- total of Rs.9000/- and the balance of Rs.6000/- may be found next -- year. In this connection I beg to state that there are numerous demands on the limited grant of Rs.10000/- allotted from the State Grant and the amount has to be left in tact for meeting the many -- existing urgent items of work.

I have the honor to be,

Sir,

Your most obedient servant,

Assistant Commissioner
for Muzrai Commissioner.

APP. F. VI. Gl.]

SUBJECT.....

.....

.....

Section

File No.

Diary No. of letter replied to.....

Seria No. 12

No.

To

.....

General and Revenue Secretariat

( )

the *192*

Date of issue.....7-9-26.....

Signed by.....

List of enclosures.....

Copied by.....

Examined by.....

over

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE.

In reply please refer to No.411 TADB

Comptroller's Office, Bangalore,

Dated the 14th Septr. *1926.*

GEN. & REV. SECTT. PR. Muz. 0 15. SEP. 1926 G. D. SECTION.

OFF. & REV. SECRETARIA. 17 SEP 1926 MUZRAI

To

C. Ranganatha Rao Saheb Esq., B.A., B.L.,
Secretary to the Government of Mysore,
Revenue Department, Bangalore.

Sir,

With reference to your letter No.469/Muz.79-24 dated 7th September 1926, I have the honor to inform you that the Chattram Savings Fund had a credit balance of Rs.20,677-3-8 on 30th June 1926 and there are no charges at present to be met from the balance of the institution.

I have the honor to be,
Sir,
Your most obedient servant,

Offg. Deputy Comptroller.

MSR

Proceedings of the Government of H.H.

the Maharaja of Mysore.

Read:-

G.O. No. 1-9/P.P. 197-18-3, dated (Camp Mysore, 9th June 1919, sanctioning the purchase at a cost of Rs. 30,000 of a building near Hanumanghat at Benares for the location of the Mysore State Chattram at the ~~Mysore~~ place.

2. D.O. No. 496, dated 17th June 1926, from Mr. S.H. Lakshminarasappa, Assistant to the Chief Engineer of Mysore, returning after scrutiny, plans and estimate for - - Rs. 15,000 prepared by the Engineer and - - Contractor Mr. R.N. Ray of Benares, for the construction of a new Chattram building in place of the present building which was completely damaged by heavy rains in September 1924.

3. Correspondence ending with letter No. P.C. 36 of 25-26, dated 26th August 1926 from the Municipal Commissioner in Mysore, stating that a sum of Rs. 2,500 out of the x amount available at the credit of the - - Chattram together with a sum of Rs. 6,500 from the Chattram Savings Fund may be spared during the current year towards the cost of the estimate and the balance of Rs. 6,000 found next year.

Order No. 675-7 Enclosures
one sanctioned estimates & plans & M.B.
Bangalore, dated 9th October 1926.

+ an abstract-estimate & E. & comptroller

The Chattram building now reported as damaged was purchased in June 1919 for - - Rs. 30,000 out of the savings of certain

chattrams and charities in the State. Since then a sum of nearly Rs. 3,000 has been spent on its repairs. The damage done to the building during the heavy rains of September 1934 made it ~~unless~~ for the purposes of a chattram and it was estimated that it would cost - - Rs. 25,000 to Rs. 30,000 to repair~~s~~. As the institution has hardly any money at its credit, Government consider that it will be sufficient to have a smaller building on the site at a cost not exceeding Rs. 15,000. An estimate for -- Rs. 15,000 for a suitable building has accordingly been obtained from Mr. Roy, Local Contractor of Benares and scrutinised by the ~~Archaeological Assistant to the Chief Engineer.~~ Architectural

2. Government are pleased to accord sanction to the said estimate Rs. 2,500 out of the - - estimated cost will be met from the balance of Rs. 2,778 at the credit of the Benares chattram and the rest viz., Rs. 12,500 from the amount at the credit of the Chattram Savings Fund.

3 The Muzrai Commissioner is requested to entrust the work to Mr. R.N. Roy, who will be ~~requested~~ asked to submit Mr. Lakshminarasappa's plan to the Municipal Council of Benares for approval before carrying out the work.

5/10

Secy. ~~to Govt.~~,
Finl. Deptt.

5/10/26

To

The Muz. Comr. in Mysore.
The Chief Engineer of Mysore ~~returning plans and estimate.~~
The Comptroller

Proceedings of the Government of His Highness

the Maharaja of Mysore.

Read:-

Government Order No. 1-9/ . . 1917-18-5, dated (illegible) Mysore 9th June 1919, sanctioning the purchase at a cost not exceeding Rs. 30,000 of a building near Hanumanghat at Benares for the location of the - Mysore State Chattram at the place.

2. D.O. letter No. 496, dated 17th June 1926, from the - - Assistant to the Chief Engineer of Mysore, returning the scrutiny plans and estimate for Rs. 15,000 prepared by the Engineer and - - Contractor Mr. R.N. Roy of Benares, for the construction of the Chattram building in place of the present building damaged by heavy rains in September 1924.

3. Correspondence ending with Letter No. .C. 36 of 5-6, dated 26th August 1926, from the Muzrai Commissioner in Mysore, stating that a sum of Rs. 2,500 out of the amount available to the credit of the Chattram together with a sum of Rs. 6,500 from the Chattram Savings Fund may be spared during the current year to defray the cost of the estimate and the balance of Rs. 6,000 could next year.

Order No.

Hotel, Bangalore, October 1926.

The estimate for Rs. 15,000 is sanctioned. Rs. 8,500 out of the estimated cost will be met from the balance of Rs. 2,778 at the credit of the Benares Chattram and the rest viz., Rs. 1,500 from the amount at the credit of the Chattram Savings Fund.

2. The Muzrai Commissioner is requested to entrust the work to Mr. R.N. Roy, who will be asked to submit Mr. L. Krishna Rao's plan to the Municipal Council of Benares for approval before - - carrying out the work.

By Order,

For Secretary to Government,
Financial Department.

To
The Muzrai Commissioner in Mysore with the estimate and plan.
The Chief Engineer of Mysore.
The Comptroller to Government.

Abstract estimate for the construction of Mysore Chattram building at Hanumanghat, Benares.

Items of work.	Per.	Rate.	Quantity	Cost
				Rs.
1. Dismantling brick work.	Lump sum			50
2. Earth work excavation.	C.ft	6--8-0	5825	38
3. Earth filling in basement.	Do.	10 0 0	2324	23
4. Concrete work in foundation.	do.	30 0 0	1694	508
5. First class brick work in cement and sand foundation.	do.	48 0 0	3882	1863
6. First class brick work in cement superstructure	c.ft.	49 0 0	4602	2255
7. First class brick work in cement 2nd floor.	..	53 0 0	2444	1295
8. Archwork.	,,	53 0 0	344	182
9. R.B. slabs for sills etc.	,,	1 4 0	120	150
10. Plastering with cement and sand	Sq.	6 0 0	92.45	555
11. First class pointing with cement.	Sq.	5 8 0	509	28
12. Moulding in Basement	Rft.	0 4 0	474	119
13. 10" cornice outside.	Rft.	0 12 0	129	97
14. Chamfering soft and jambs of doors etc.	do 100	12 8 0	543	68
15. Flooring 4" R.B. Terrace over 4" Brick flat.	Sq.	25 0 0	1304	326
16. Roofing 3" R.B. slab and 4" concrete and terracing rendered smooth with lime.	Sq.ft.	65 0 0	794	516
17. Roofing with 5" R.B. slab and 4" concrete terracing rendered smooth with lime.	do.	80 0 0	1372	1098
18. Surface drain.	R.ft.	0 10 0	150	94
19. Ornamental dome complete.	each.	300 0 0	2	600
20. Copper finials gilded	do.	50 0 0	2	100
21. Parapet ornamental with finials at intervals complete.	Rft.	3 8 0	226	791
22. Lovey with R.B. slabs.	Sq.	30 0 0	525	158
23. Stone brackets 2' apaiet	cft.	5 0 0	63	315
24. Moulding with dental cornice below tower inside.	Rft.	1 0 0	80	80
25. White washing.	Sq.	0 8 0	9245	46
26. Stone brackets below windows tower rooms.	each	8 0 0	16	128
27. Stone pillars ornamental or reinforced complete with capital and base Ground floor.	do.	60 0 0	6	360
28. Stone pillars ornamental or reinforced complete with capital and base 2nd floor.	do.	50 0 0	6	300
29. Ornamental small turrets at corners or dome ..	do.	15 0 0	8	120
30. Vimanams	do.	15 0 0	8	120
31. Plain square moulding around doors and windows.	Rft.	0 2 0	1097	137
32. Teakwood doors venetion and panelled shutters complete.	Sft.	2 3 0	319	698
33. Teakwood windows with single shutters in 4 halves on the outside 1" think bottom shutters being panelled and top Glazed with round iron bars.3/4" thick.	Sft.	3 0 0	270	810
34. C.I.Ventilator. 8" x 8"	each	2 0 0	10	20
35. Painting.	Sft.	5 12 0	1448	81
36 Stone pitching	Syd.	2 0 0	33	66
37. Rolled steel beams for verandah over pillars.	Cwt.	12 8 0	28	370

			Rs.
38. Clearing site.	Lump sum.		50
		Rs.	14,594
	for contingencies and unforseen charges.		406
		Total.	15,000

Copy.

Superintendent,
Muzr. 1 Branch.